

NOTES:

- 1. ALL EXPOSED CONCRETE SHALL HAVE A BROOM FINISH.
- 2. EXPANSION JOINTS SHALL BE INSTALLED AT 500 FOOT MAXIMUM INTERVALS, SEE CURB EXPANSION JOINT DETAIL.
- 3. CONTRACTION JOINTS SHALL BE INSTALLED AT END OF CURB RETURNS AND AT 10 FOOT MAXIMUM INTERVALS SEE CURB CONTRACTION JOINT DETAIL.
- 4. WHEN JOINING EXISTING CURB, PROVIDE A MINIMUM OF THREE $\#4 \times 16$ " DOWELS (9" EMBEDMENT) EVENLY SPACED.
- ★ 5. WHEN PLACING CURB ADJACENT TO CONCRETE PAVEMENT, THICKEN GUTTER TO MATCH PAVEMENT DEPTH.

DRAWN BY: JSH
CHECKED BY: WGH

APPROVED BY:
DIRECTOR OF PUBLIC WORKS

CITY OF BOULDER, COLORADO

INTEGRAL CURBWALK

ISSUED: JULY 2, 1998
REVISED: OCT 6, 2009

DRAWING NO.

2.02.B