

- 1. ALL EXPOSED CONCRETE SHALL HAVE A BROOM FINISH.
- 2. EXPANSION JOINTS SHALL BE INSTALLED AT 500 FOOT MAXIMUM INTERVALS SEE EXPANSION JOINT DETAIL.
- 3. CONTRACTION JOINTS SHALL BE INSTALLED AT END OF CURB RETURNS AND AT 10 FOOT MAXIMUM INTERVALS SEE CURB CONTRACTION JOINT DETAIL.
- 4. WHEN JOINING EXISTING CURB, PROVIDE A MINIMUM OF THREE #4 x 18" DOWELS (9" EMBEDMENT) EVENLY SPACED.
- \* 5. WHEN PLACING CURB ADJACENT TO CONCRETE PAVEMENT, THICKEN GUTTER TO MATCH PAVEMENT DEPTH.

DRAWN BY: JSH
CHECKED BY: RJH

CITY OF BOULDER, COLORADO

REVISED: OCT 6, 2009

ISSUED: JULY 2, 1998

APPROVED BY: DIRECTOR OF PUBLIC WORKS

CURB AND GUTTER

DRAWING NO.

2.01.A